



HAYWOOD

COUNTY SCHOOLS

MAINTENANCE
401 Farmview Drive, Waynesville, NC 28786
P: 828.456.2402 | F: 828.456.2452

Maintenance Director: Josh Mease

ADDENDUM #1

April 12, 2021

TO: ALL POTENTIAL BIDDERS
FROM: JOSH MEASE, MAINTENANCE DIRECTOR
SUBJECT: WAYNESVILLE MIDDLE SCHOOL B BUILDING
HVAC ELECTRICAL

(RFP# 7-21)

The following specifications are hereby made a part of the original documents. Bidders shall acknowledge receipt of this addendum by notation in the space provided on the Proposal Form.

Addendum includes: New Bid Date and Adding a Third Base Bid

Addendum #1
RFP# 7-21



ADDENDUM to RFP# 7-21

Waynesville Middle School B Building HVAC Electrical

Include:

- New Bid Opening Date will be Monday, April 19, 2020 at 1:00 pm EST.
- BASE BID #3
 - Contractor will install a 1” conduit from the new panel to each set of HVAC units set in the coves per sketch drawing. Contractor will penetrate the exterior wall and install a Nema 3R junction box on each conduit. Total of eight (8) conduits.
 - Contractor will be responsible for checking out a key from the Maintenance Department.
 - Contractor will be responsible for pulling all permits.
 - Contractor will provide and install all materials.
 - Proposal does not include wire to each location.
 - Contractor will be responsible for installing pull strings in each pipe.
 - This is an evening project. Work may not begin until 2:00 pm Monday through Friday and must be out of the building by 6:00 am. Work may be completed at any time on Saturday or Sunday.
 - Contractor will relocate single-phase breaker downstairs to the existing panel upstairs.

If there are any questions, please call David Earley at (828) 734-6062.